BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/03/2014-15, Date:31.10.2014.

ITEM NO: 25

SCHEDULE-B

NAME OF WORK: Improvements to Footpath 17th 'A' & 17 'B' cross roads Opp. Geetha School, in Ward no. 13, in Shettyhalli Sub-Division.

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor **B MUNIRAJU**	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications with all leads and lifts etc., Complete as per specification and direction of Engineer-in-charge of the work.	Cum	310.8	73.67	Rupees Seventy Three and Sixty Seven Paise Only
2	Providing and laying in position plain cement concrete of mix M10 with cement @ 180 kg with 40mm and down size graded granite metal coarse aggregates @ 0.86Cum and fine aggregates @ 0.58cum, machine mixed, concrete laid in layers not exceeding 15 cm thick, well compacted in foundation and plinth including cost of all materials, labour, HOM of machinery, curing etc., Complete as per specification and direction of Engineer-in-charge of the work.	Cum	47.25	4723.44	Rupees Four Thousand Seven Hundred Twenty Three and Forty Four Paise Only
3	Removing B.S. slab of drain and stacking with all leads and lifts etc., Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	317.48	56.83	Rupees Fifty Six and Eighty Three Paise Only
4	Refixing stone slabs of drains and pointing in CM 1:3 with all leads and lifts etc., Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	317.48	73.67	Rupees Seventy Three and Sixty Seven Paise Only
5	Providing Granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	16.34	623.05	Rupees Six Hundred Twenty Three and Five Paise Only

B. Munirju
Signature of the Contractor

Executive Enginee

6	Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	280	968.26	Rupees Nine Hundred Sixty Eight and Twenty Six Paise Only
7	Providing and constructing precast concrete solid blocks with compressive strength not less than 3.5 Newton per sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x15x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications with all leads and lifts etc., Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	280	916.69	Rupees Nine Hundred Sixteen and Sixty Nine Paise Only
8	Providing flush pointing to square rubble, course or uncoursed stone masonary with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm, nicely lining, including cost of materials, labour, curing Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	280	89.45	Rupees Eighty Nine and Forty Five Paise Only
9	Providing and laying in position plain cement concrete of mix M 15 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing Complete as per specification and direction of Engineer-in-charge of the work.	Cum	14	5191.78	Rupees Five Thousand One Hundred Ninety One and Seventy Eight Paise Only
10	Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	630	1559.2	Rupees One Thousand Five Hundred Fifty Nine and Twenty Paise Only
11	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 3 Km a)Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b)Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c)Add loading and unloading Complete as per specification and direction of Engineer-in-charge of the work.	Cum	310.8	73.54	Rupees Seventy Three and Fifty Four Paise Only

B. Manjula
Signature of the Contractor

Executive Engineer,
Dasarahalli Division,